

RADION receiver SD

B810



RADION receiver SD Table of contents | en 3

Table of contents

1	Introduction	4
1.1	Requirements	4
1.2	About documentation	4
2	Version 3.01 firmware	5
2.1	Whats new	5
2.1.1	Maintenance update	5
2.2	Known issues	5
2.2.1	Reduced signal margins	5
3	Version 2.01 firmware	6
3.1	What's new?	6
4	Determine the firmware version of the B810 receiver	7
5	Firmware upgrade instructions	
6	Revision history	11

4 en | Introduction RADION receiver SD

1 Introduction

These Release Notes are for the RADION receiver SD with firmware version 3.01.

1.1 Requirements

There are no additional requirements for firmware version 3.01 as this firmware is already installed.

1.2 About documentation

Copyright

This document is the intellectual property of Bosch Security Systems B.V. and is protected by copyright. All rights reserved.

Manufacturing dates

For product manufacturing dates, go to http://www.boschsecurity.com/datecodes/ and refer to the serial number located on the product label.

Trademarks

All hardware and software product names used in this document are likely to be registered trademarks and must be treated accordingly.

2021.07 | 03 | F.01U.316.548 Release notes Bosch Security Systems B.V.

RADION receiver SD Version 3.01 firmware | en 5

2 Version 3.01 firmware

Firmware v3.01 is installed on RADION receiver SD (B810), SDI2 bus compatible receivers.

Whats new

- Maintenance update, page 5

Known issues

- Reduced signal margins, page 5

Refer to

- Determine the firmware version of the B810 receiver, page 7

2.1 Whats new

This section examines the new features of this firmware version.

2.1.1 Maintenance update

Software updates are included in this firmware update to support new circuitry components on the B810 receiver.

2.2 Known issues

This section examines the known issues of this firmware version.

2.2.1 Reduced signal margins

Signal margins might be lower due to the use of new hardware components in the receiver. If you experience reliability and performance issues, install in a location with low radio noise. Consider installing a repeater if the receiver must be installed in a high-noise environment. For installation considerations, refer to the B810 Reference Guide (F01U261834), Chapter 2 General Installation.

6 en | Version 2.01 firmware RADION receiver SD

3 Version 2.01 firmware

Firmware v2.01 is available for the RADION receiver SD (B810), SDI2 bus compatible receiver.

3.1 What's new?

This section examines the new features of this firmware version.

This firmware enables support for the following RADION key fobs using synchronized encryption:

- RFKF-FBS/RFKF-FBS-A/RFKF-FBS-CHI
- RFKF-TBS/RFKF-TBS-A/RFKF-TBS-CHI



Notice!

B810 receiver firmware version v2.01 or higher is required when using these RADION key fob products.

4 Determine the firmware version of the B810 receiver

The receiver and the receiver's box show the original firmware version installed during manufacturing. You can use the RPS diagnostics feature to determine the B810 firmware version at any time. The B810 must be connected to a compatible control panel. Refer to the figures to locate and determine your receiver's original firmware version.




Figure 4.1: B810 box label and firmware version

Callout — Description

- 1 Receiver box
- 2 Receiver box label
- 3 Receiver firmware version




Figure 4.2: Receiver lable

Callout — Description

- 1 Receiver
- 2 Receiver label
- 3 Receiver firmware version

5 Firmware upgrade instructions

Refer to the table below for compatible control panel firmware versions that support upgrading B810 firmware through RPS.

Notice!



Possible false jamming receiver signals when firmware version 2.01 is installed onto a receiver with version 3.01 firmware or higher

Avoid installing firmware version 2.01 onto a receiver that currently has firmware version 3.01 installed. Doing so causes the receiver to inaccurately calculate the signal strength at a higher level and might cause the receiver to think the signal is being jammed. Refer to *Determine the firmware version of the B810 receiver, page 7* section for information on locating your receiver's firmware version.

Compatible control panel firmware versions

Compatible control panel	Control panel firmware version
B9512G/B9512G-E B8512G/B8512G-E	v3.00 or higher
B6512/B5512/B4512/B3512 B5512E/B4512E/B3512E	v2.01 or higher
D9412GV4/D7412GV4	v2.02 or higher

Compatible RPS versions

RPS must be at v5.17 or higher in order to perform a firmware upgrade to the B810 receiver. Read all applicable RPS and control panel release notes prior to upgrading. Failure to do so might cause incompatibility issues.

Perform the following steps to download the firmware.

Download the firmware from the website

Downloading the firmware:

- 1. Locate the firmware file (.fwr extension) for the B810 located on the RADION receiver SD product/software download web page at: www.boschsecurity.com.
- 2. Select North America.
- 3. Select country of origin (USA or Canada).
- 4. Select Products from the pull-down menu and choose Intrusion Alarm Systems.
- Select Premise Wireless.
- 6. Select RADION.
- 7. Scroll down and select RADION receiver SD.
- 8. Select the Software Downloads tab.
- 9. Locate the firmware file (.fwr extension).
- 10. Save the file to your computer, and to a directory to which RPS has access.

Import the .fwr file into RPS

Perform the following steps to import the .fwr file into RPS.



Notice!

The B810 receiver must be connected to a supporting control panel in order to upload the firmware.

 Bosch Security Systems B.V.
 Release notes
 2021.07 | 03 | F.01U.316.548

- 1. Launch RPS.
- 2. Select Config from the top menu area, and then System.
- 3. Select the Firmware Files tab.
- 4. Select Import.
- 5. Select the box next to Select Firmware File to navigate and locate the saved .fwr file.
- 6. Select the .fwr file and select Open.
- 7. Follow the wizard to complete the import.

Update the receiver using RPS

Updating the receiver:

- 1. Select the appropriate control panel account and connect to it.
- 2. Use the Firmware Update Wizard to update the B810 receiver with the imported firmware file. Refer to RPS Help for detailed instructions.

RADION receiver SD Revision history | en 11

6 Revision history

This section examines the notable features of previous revisions of this firmware.

Bosch Security Systems B.V. Release notes 2021.07 | 03 | F.01U.316.548

12 | Revision history RADION receiver SD



Bosch Security Systems B.V.

Torenallee 49 5617 BA Eindhoven Netherlands

www.boschsecurity.com

© Bosch Security Systems B.V., 2021